



Notes:

UNLESS NOTED OTHERWISE, ALL JOISTS ARE TO BE 2X6 #2 SYP. OR EQUAL.
ALL JOISTS SHALL BE SPACED AT 16" O.C.

ALL HEADDERS SHALL BE 2X8 #2 SYP W/ 7/16" OSB FILLER.
WHERE REQUIRED SECURE JOISTS WITH METAL JOIST HANGERS.
CROSSBRIDGE ALL SPANS AS SHOWN.
DOUBLE JOISTS UNDER PARRALEL PARTITIONS.

— DENOTES BEAM (2-2X12 #2 SYP W/ 7/16" OSB FILLER; GLUED AND NAILED)

SET WINDOW HEADDERS @ 6'-8" A.F.F.
SET DOOR HEADDERS @ 6'-11" A.F.F.
PROVIDE 2X10 JOISTS AT AREA WHERE HVAC UNIT IS LOCATED.
DECK AN 8'X8' AREA FOR UNIT AND REPAIR PLATFORM.

JOISTPLAN

SCALE: 3/8" = 1'

Nesvadba Design Services

P.O. Box 353, Texas, 77461
Phone: 281.543.4660
E-mail: ags96@consolidated.net

Sheet No.

S3

of 12

Needville Youth Fair
Administration Building Improvement